

JACK AHEARN 20 PARK ROAD

BRIARCLIFF MANOR, NY, 10510 3451 LEXINGTON AVE CORTLANDT, NEW YORK, 10547 HC, HIGHWAY COMMERCIAL

TOWN TAX MAP DATA: SEWAGE FACILITIES:

AUTO STORAGE SECTION 13.19, BLOCK 2, LOT 2 16.55 ACRES (720,911 SF) ONSITE SSTS PUBLIC WATER FACILITIES

HC - Highway Commercial REQUIRED <u>PROVIDED</u> 20,000 SF. 720,911 SF. NONE 100 FT. 407.4 FT. NONE 30 FT. 37.5 FT. NONE 30 FT. NONE 706.6 FT. 30 FT. NONE 48.2 FT.

MINIMUM LOT WIDTH: MINIMUM YARD DIMENSIONS: PRINCIPAL BUILDING: FRONT YARD SETBACK: REAR YARD SETBACK: SIDE YARD SETBACK: ACCESSORY BUILDINGS: 30 FT. FRONT YARD SETBACK: 267.9 NONE 30 FT. REAR YARD SETBACK: 644.9 FT. NONE 30 FT. NONE SIDE YARD SETBACK: 62.2 FT. MAXIMUM % OF LOT TO BE OCCUPIED: PRINCIPAL BUILDING COVERAGE: 20% OF LOT AREA 4.9 % OF LOT AREA NONE NONE 144,182.20 SF 34,880 SF MAXIMUM HEIGHT: PRINCIPAL BUILDING - FEET: 35 FEET NONE PRINCIPAL BUILDING - STORIES: 2 1/2 NONE NONE ACCESSORY BUILDING - FEET: XX


ZONING REGULATION NOTES:


1. NO SINGLE USE, OTHER THAN A FOOD STORE, SHALL OCCUPY MORE THAN 4,000 SQUARE FEET.


2. THREE-AND FOUR-DWELLING S ARE LIMITED TO NO MORE THAN TWO BEDROOMS PER UNIT. 3. EXISTING BUILDINGS WITH MORE THAN 20,000 SQUARE FEET PER FLOOR SHALL BE CONSIDERED


DIMENSIONALLY NONCONFORMING AS PER 307-81 OF THE TOWN OF CORTLANDT ZONING CODE.


ZONING DISTRICT: VARIANCE REQUIRED **DIMENSIONAL REGULATIONS:** MINIMUM SIZE OF LOT: MINIMUM LOT AREA: NONE ACCESSORY BUILDING - STORIES: XX















DISTANCE ALONG BASELINE (FT)

PROPOSED MAIN DRIVE VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50




DISTANCE ALONG BASELINE (FT)


FRONT DRIVE VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50

PRELIMINARY SITE PI PREPARED FOR LEXINGTON

C-301


SAFE DIG Before You Dig, Drill or Blast!
CALL US TOLL FREE 811 or 1-800-962-7962
NY Industrial Code Rule 753 requires no less than two working days notice, but not more than ten days notice.





DISTANCE ALONG BASELINE (FT)

CB-1 TO CB-7 VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50



DISTANCE ALONG BASELINE (FT)

CB-8 TO OUTLET VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50

DISTANCE ALONG BASELINE (FT)

CB-11 TO CB-10 VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50

THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY DANIEL T. MERRITTS, DATED 6/10/19, LAST REVISED 7/8/19. THE TOPO SHOWN BEYOND THE BORDERS OF THE SURVEY HAVE BEEN SAFE DIG Before You Dig, Drill or Blast!

CALL US TOLL FREE 811 or 1-800-962-7962

NY Industrial Code Rule 753 requires no less than two working days notice, but not more than ten days notice.

www.digsafelynewyork.com

C-302

AQUIRED FROM THE WESTCHESTER COUNTY GIS WEBSITE. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF EITHER TOPO SOURCE.

Consultants

H

PROFIL

PRELIMINARY SITE PLAN
PREPARED FOR
LEXINGTON AVENU

GENERAL NOTES:

- 1. THE ENGINEER WHOSE SEAL APPEARS HEREON HAS NOT BEEN RETAINED FOR SUPERVISION OF CONSTRUCTION, SUBSEQUENTLY,HE IS NOT RESPONSIBLE FOR CONSTRUCTION AND THEREFORE ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION PRACTICES, PROCEDURES, AND RESULTS THEREFROM.
- 2. THE ENGINEER SHALL NOT BE HELD RESPONSIBLE OR HELD ACCOUNTABLE FOR THE INTEGRITY OF ANY STRUCTURES CONSTRUCTED OR UNDER CONSTRUCTION PRIOR TO THE APPROVAL OF THE PLANS.
- THE TOWN ENGINEER'S OFFICE AND WATER DISTRICT OFFICE IS TO BE NOTIFIED 24 HOURS BEFORE COMMENCING SITE CONSTRUCTION OR WATER MAIN CONNECTION.
- 4. ALL WORK IS TO BE IN ACCORDANCE WITH THE TOWN CODE OF PRACTICE AND SPECIFICATIONS.
- 5. ALL CONDITIONS, LOCATIONS, AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED OF ANY DISCREPANCIES. 6. ALL CHANGES MADE TO THE PLANS SHALL BE APPROVED BY THE ENGINEER WHOSE SEALAPPEARS ON THESE DRAWINGS. ANY SUCH CHANGES SHALL BE
- FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT.
- 7. ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED DIMENSIONS
- 8. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL IN A "CODE 53" PRIOR TO CONSTRUCTION FOR UNDERGROUND UTILITY LOCATIONS. 9. SUBSTRUCTURES
- AND THEIR ENCROACHMENTS BELOW GRADE, IF ANY, ARE NOT SHOWN. 9. ANY PROPOSED ELECTRIC AND/OR TELEPHONE SERVICE LINES ARE TO BE PLACED UNDERGROUND.
- THE DESIGN ENGINEER DISCLAIMS ANY LIABILITY FOR DAMAGE OR LOSS INCURRED DURING OR AFTER CONSTRUCTION.
- 11. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY.

CONTRACTOR RESPONSIBILITIES:

- 1. ALL WORK ON THE PROJECT SHALL BE PERFORMED IN A WORKMAN LIKE MANNER AND SHALL BE IN ACCORDANCE WITH THE STANDARDS OF THE INDUSTRY. THE OWNER WILL BE THE SOLE JUDGE OF THE ACCEPTABILITY OF THE WORK. MATERIALS AND WORK DEEMED UNACCEPTABLE WILL BE REMOVED AND REDONE AT THE SOLE COST AND RESPONSIBILITY OF THE CONTRACTOR.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT HIS WORK AND WILL BE HELD RESPONSIBLE FOR CONSEQUENTIAL DAMAGES DUE TO HIS ACTIVITIES. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEE, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY THE WORK UNDER A SEPARATE CONTRACT WITH THE CONTRACTOR.
- 3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROPERLY SHORE EXISTING UTILITIES IF REQUIRED BY CONSTRUCTION.
- 4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE THE BUILDING INSPECTOR IN ADVANCE OF HIS WORK OR AS THE INSPECTOR DEEMS 5. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY
- DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY. 6. ALL CHANGES MADE TO THIS PLAN SHALL BE APPROVED BY THE ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS. ANY UNAUTHORIZED ALTERATION OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.
- 7. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THIS
- CONTRACT 8. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEES, SUBCONTRACTORS, AND THEIR AGENTS
- AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY OF THE WORK UNDER A CONTRACT WITH THE CONTRACTOR. 9. THE CONTRACTOR SHALL VERIFY ALL SUBSTRUCTURES ENCOUNTERED DURING CONSTRUCTION.
- 10. THE CONTRACTOR SHALL SECURE & PAY FOR A BUILDERS RISK POLICY TO COVER THE PERIOD OF CONSTRUCTION. THE ENGINEER & OWNER SHALL BE NAMED AS ADDITIONAL INSURED. ALL CONTRACTORS EMPLOYED AT THE SITE SHALL BE COVERED BY WORKMAN'S COMPENSATION.

GENERAL CONSTRUCTION NOTES:

- 1. BENCH MARKS USING U.S.G.S. DATUM SHALL BE OF SUCH ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS. 2. CONSTRUCTION ACTIVITY SHALL BE LIMITED FROM 8:00 A.M. TO 6 P.M., AND NO CONSTRUCTION ACTIVITY SHALL OCCUR ON SUNDAYS OR LEGAL NEW YORK STATE HOLIDAYS. WHERE BLASTING IS NECESSARY, IT SHALL OCCUR FROM MONDAY THROUGH FRIDAY BETWEEN THE HOURS OF 8:00 A.M. AND 6:00 P.M. NO BLASTING SHALL OCCUR ON HOLIDAYS, SATURDAY OR SUNDAY. ALL BLASTING SHALL ALSO BE COMPLETED IN ACCORDANCE WITH THE TOWN OF OSSINING AND NEW YORK STATE BLASTING ORDINANCES.
- 3. ANY SOIL THAT IS UNSUITABLE FOR DEVELOPMENT OF BUILDINGS OR ROADWAYS SHALL BE REMOVED FROM AREAS TO BE DEVELOPED AND SHALL BE DISPOSED OF WITHIN THE SITE IN NEW EMBANKMENTS WHERE STRUCTURAL LOADING, I.E. A BUILDING OR ROADWAY, WILL NOT TAKE PLACE. WHEN CONSTRUCTION IS PROPOSED TO OCCUR IN SPECIFIC AREAS WHERE SOILS ARE OF QUESTIONABLE SUITABILITY, THE APPLICANT SHALL PROVIDE SOILS ENGINEERING REPORTS AS REQUIRED BY THE PLANNING BOARD ENGINEER, PRIOR TO THE CONSTRUCTION OF ROADWAYS AND, AS REQUIRED BY THE BUILDING INSPECTOR, PRIOR TO THE ISSUANCE OF A BUILDING PERMIT.
- 4. NO TOPSOIL SHALL BE REMOVED FROM THE SITE.
- 5. ROCK CUT STABILITY IS TO BE FIELD VERIFIED BY GEOTECHNICAL ENGINEER AND SHALL BE MODIFIED IF REQUIRED. 6. NO CRUSHING/PROCESSING IS PERMITTED ON THE SITE WITHOUT PRIOR APPROVAL BY THE TOWN OF OSSINING PLANNING BOARD.

GENERAL STORM DRAINAGE & UTILITY NOTES

- 1. ALL UTILITIES, INCLUDING ELECTRIC LINES, TELEPHONE, WATER, SANITARY SEWER LINES, AND STORM SEWER LINES SHALL BE LOCATED UNDERGROUND AND SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE TOWN OF OSSINING AND THE UTILITY COMPANIES HAVING JURISDICTION.
- 2. LOCATION OF GAS AND WATER VALVES, ELECTRIC AND TELEPHONE POLES ARE TO BE DETERMINED BY PROPER AUTHORITIES AND APPROVED, AS TO LOCATION, BY THE TOWN ENGINEER. 3. EACH BUILDING CONSTRUCTED HEREON SHALL BE OF SUCH AN ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS. IN THE EVENT THAT
- THIS IS NOT FEASIBLE, THE CONTRACTOR SHALL INSTALL TYPICAL YARD DRAINS AS REQUIRED AND CONNECT THEM TO THE STORM DRAINAGE SYSTEM OR AS
- 4. ROOF LEADERS AND FOOTING DRAINS SHALL EMPTY INTO THE STORM DRAINAGE SYSTEM OR DISCHARGE DIRECTLY TO STORMWATER MANAGEMENT SYSTEMS IF GRADES PERMIT, AND CONNECTION TO THE STORM SYSTEM IS NOT FEASIBLE, FOOTING DRAINS ONLY MAY DISCHARGE TO DAYLIGHT AT THE REAR OF BUILDINGS. FOOTING DRAINS SHALL EXTEND A MINIMUM OF 30 FT. FROM THE REAR FACE OF THE BUILDING WHEN POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE DISCHARGE OF GROUND WATER OR STORM WATER, EITHER BY GRAVITY OR BY PUMPING, BE DISCHARGED TO ANY SANITARY SEWER SYSTEM
- 5. ANY REVISIONS AND/OR ADDITIONS TO THE ROAD STORM DRAINAGE SYSTEMS CURRENTLY SHOWN ON THE PLANS WHICH ARE DEEMED NECESSARY DURING CONSTRUCTION MUST BE MADE BY THE CONTRACTOR AS REQUIRED BY THE TOWN AND SHALL BE SHOWN ON THE AS-BUILT DRAWINGS.
- 6. STORM DRAIN PIPING TO BE HIGH DENSITY POLYETHYLENE AS SHOWN ON THE CONSTRUCTION DRAWINGS. MINIMUM COVER TO BE 2' UNLESS OTHERWISE
- 7. INTERCEPTOR DRAINS ARE TO BE INSTALLED WHERE REQUIRED BY THE TOWN OR PROJECT ENGINEER DURING ROAD CONSTRUCTION.
- 8. ALL EXISTING UNDERGROUND DRAINS ENCOUNTERED DURING CONSTRUCTION OF PROPOSED ROADS ARE TO BE CONNECTED TO PROPOSED DRAINAGE IMPROVEMENTS. CONNECTIONS TO BE APPROVED BY THE TOWN ENGINEER.
- 9. PRIOR TO FINAL APPROVAL AND OPERATION OF DRAINAGE SYSTEM, CONTRACTOR SHALL CLEAR ALL ACCUMULATED SEDIMENT AND/OR DEBRIS FROM DRAINAGE STRUCTURES, MANHOLES, CULVERTS, OUTLETS AND DRAIN INLETS. ENGINEER SHALL BE NOTIFIED FOR FINAL INSPECTION.
- 10. ALL STRUCTURES SHALL BE SET ONE INCH BELOW PAVEMENT. 11. STREET OPENING PERMIT FROM THE TOWN OF OSSINING D.P.W. MAY BE REQUIRED FOR INSTALLATIONS IN PUBLIC ROADS.

WALL NOTES:

- 1. EXCAVATION IN GENERAL SHALL CONFORM TO THE LINES AND GRADES SHOWN ON THE CONTRACT DRAWINGS.
- 2. THE ENGINEER SHALL BE NOTIFIED OF UNSUITABLE SUB-GRADE SOILS PRIOR TO PLACEMENT OF WALL. 3. WALLS TO BE CONSTRUCTED ON VIRGIN IN-SITU SOIL SHALL HAVE A MINIMUM ALLOWABLE BEARING CAPACITY OF 2 TSF. ALL OTHER CONDITIONS SHALL BE
- APPROVED BY THE GEOTECHINICAL ENGINEER.
- 4. TO INSURE A PROPER BEARING SURFACE, THE WALL SHALL BE CONSTRUCTED ON NATURAL IN-SITU SOIL, THE CONTRACTOR SHALL STRIP ALL TOP SOIL. THE AREA SHALL THEN BE COMPACTED USING SUITABLE COMPACTION EQUIPMENT. A MINIMUM OF 3 PASSES SHALL BE MADE.
- 5. WALLS SHALL NOT BE CONSTRUCTED ON WET OR FROZEN GROUND. 6. SOILS USED AS BACKFILL SHALL CONSIST OF CLEAN DRY SOIL. THE MATERIAL SHALL BE GRANULAR AND FREE OF ORGANIC OR OTHER DELETERIOUS MATERIAL. IN
- GENERAL THE SOIL SHALL BE NON- PLASTIC WITH A PLASTICITY INDEX LESS THAN 5 AND SHALL CONFORM TO THE AASHTO SOIL CLASSIFICATION SYSTEM FOR AN "A-1-A" SOIL . HOWEVER THE MAXIMUM SIZE SHALL BE 6". IN GENERAL ALL FILL SHALL BE APPROVED BY THE ENGINEER PRIOR TO IT'S USE. WET MATERIAL OR UNSUITABLE MATERIAL SHOULD NOT BE USED.
- 7. BACKFILL SHALL BE PLACED AND COMPACTED IN A MAXIMUM 12" LIFTS.
- 8. ALL BOULDER RETAINING WALLS SHALL HAVE A GEOTEXTILE FABRIC BACKING FOR THE FULL HIEGHT OF THE WALL AS MANUFACTURED BY MIRAFI OR APPROVED
- 9. IF GROUNDWATER IS ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY TO DETERMINE IF THE ADDITION OF AN UNDERDRAIN MAY BE REQUIRED. 10. THE CONTRACTOR SHALL NOT USE LARGE OR HEAVY CONSTRICTION EQUIPMENT WITHIN 5' OF THE RETAINING WALLS OR NEW FOUNDATION WALLS. HAND
- OPERATED COMPACTING EQUIPMENT SHALL BE USED WITHIN 5' OF THE WALL FACE. 11. ALTERNATE WALL DESIGNS MUST BE SEALED BY A NEW YORK STATE LICENSED PROFESSIONAL ENGINEER THE MINIMUM FACTORS OF SAFETY FOR SLIDING AND OVERTURNING SHALL BE 2.0.

MAINTENANCE SCHEDULE:

| | | DAILY | WEEKLY | MONTHLY | AFTER RAINFALL | NECESSARY TO MAINTAIN FUNCTION | AFTER APPROVAL OF INSPECTOR |
|--|---------------------|-------|--------|---------|-------------------|--------------------------------------|-----------------------------------|
| | SILT FENCE | | | INSP. | INSP. | CLEAN/ REPLACE | REMOVE |
| | WHEEL CLEANER | CLEAN | | | | REPLACE | REMOVE |
| | INLET PROTECTION | | INSP. | INSP. | CLEAN | REPLACE | REMOVE |

MAINTENANCE OF PERMANENT CONTROL STRUCTURES DURING CONSTRUCTION:

The stormwater management system and outlet structure shall be inspected on a regular basis and after every rainfall event. Sediment build up shall be removed from the inlet protection regularly to insure detention capacity and proper drainage. Outlet structure shall be free of obstructions. All piping and drain inlets shall be free of obstruction. Any sediment build up shall be removed.

MAINTENANCE OF CONTROLS AFTER CONSTRUCTION:

Controls (including respective outlet structures) should be inspected periodically for the first few months after construction and on an annual basis thereafter. They should also be inspected after major storm events.

Twice a year, inspect outlet structure and drain inlets for accumulated debris. Also, remove any accumulations during each mowing operation. STRUCTURAL REPAIR/REPLACEMENT

Outlet structure must be inspected twice a year for evidence of structural damage and repaired immediately.

Unstable areas tributary to the basin shall immediately be stabilized with vegetation or other appropriate erosion control measures. SEDIMENT REMOVAL

DEBRIS AND LITTER REMOVAL:

Sediment should be removed after it has reached a maximum depth of five inches above the stormwater management system floor

GENERAL EROSION CONTROL NOTES:

- 1. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL SEDIMENT AND EROSION CONTROL PRACTICES. THE SEDIMENT AND EROSION CONTROL PRACTICES ARE TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCES. AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED. ROAD SURFACE FLOWS FROM THE SITE SHOULD BE DISSIPATED WITH TRACKING PAD OR APPROPRIATE MEASURES DURING ADJACENT ROAD SHOULDER REGRADING. CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL SOIL EROSION AND
- SEDIMENTATION CONTROL DEVICES THROUGHOUT THE COURSE OF CONSTRUCTION. 2. CATCH BASIN INLET PROTECTION MUST BE INSTALLED AND OPERATING AT ALL TIMES UNTIL TRIBUTARY AREAS HAVE BEEN STABILIZED. WHEN POSSIBLE FLOWS SHOULD BE STABILIZED BEFORE REACHING INLET PROTECTION STRUCTURE. TIMELY MAINTENANCE OF SEDIMENT CONTROL STRUCTURES IS THE RESPONSIBILITY OF THE CONTRACTOR.
- 3. ALL STRUCTURES SHALL BE MAINTAINED IN GOOD WORKING ORDER AT ALL TIMES. THE SEDIMENT LEVEL IN ALL SEDIMENT TRAPS SHALL BE CLOSELY MONITORED AND SEDIMENT REMOVED PROMPTLY WHEN MAXIMUM LEVELS ARE REACHED OR AS ORDERED BY THE ENGINEER. ALL SEDIMENT CONTROL STRUCTURES SHALL BE INSPECTED ON A REGULAR BASIS, AND AFTER EACH HEAVY RAIN TO INSURE PROPER OPERATION AS DESIGNED. AN INSPECTION SCHEDULE SHALL BE SET FORTH PRIOR TO THE START OF CONSTRUCTION.
- 4. THE LOCATIONS AND THE INSTALLATION TIMES OF THE SEDIMENT CAPTURING STANDARDS SHALL BE AS SPECIFIED IN THESE PLANS, AS ORDERED BY
- THE ENGINEER, AND IN ACCORDANCE WITH THE LATEST EDITION OF THE "NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL" (NYSSESC). 5. ALL TOPSOIL SHALL BE PLACED IN A STABILIZED STOCKPILE FOR REUSE ON THE SITE. ALL STOCKPILE MATERIAL REQUIRED FOR FINAL GRADING AND
- STORED ON SITE SHALL BE TEMPORARILY SEEDED AND MULCHED WITHIN 7 DAYS. REFER TO SOIL STOCKPILE DETAILS. 6. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 7 DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, SHALL IMMEDIATELY
- RECEIVE TEMPORARY SEEDING. MULCH SHALL BE USED IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER. DISTURBED AREAS SHALL NOT BE LIMED AND FERTILIZED PRIOR TO TEMPORARY SEEDING.
- 7. ALL DISTURBED AREAS WITHIN 500 FEET OF AN INHABITED DWELLING SHALL BE WETTED AS NECESSARY TO PROVIDE DUST CONTROL. 8. THE CONTRACTOR SHALL KEEP THE ROADWAYS WITHIN THE PROJECT CLEAR OF SOIL AND DEBRIS AND IS RESPONSIBLE FOR ANY STREET CLEANING
- NECESSARY DURING THE COURSE OF THE PROJECT. 9. SEDIMENT AND EROSION CONTROL STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY
- STABILIZED BY PERMANENT MEASURES. 10. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH CURRENT EDITION OF NYSSESC.
- 11. ALL REGRADED AREAS MUST BE STABILIZED APPROPRIATELY PRIOR TO ANY ROCK BLASTING, CUTTING, AND/OR FILLING OF SOILS. SPECIAL CARE SHOULD BE TAKEN DURING CONSTRUCTION TO INSURE STABILITY DURING MAINTENANCE AND INTEGRITY OF CONTROL STRUCTURES.
- 12. ANY SLOPES GRADED AT 3:1 OR GREATER SHALL BE STABILIZED WITH EROSION BLANKETS TO BE STAKED INTO PLACE IN ACCORDANCE WITH THE MANUFACTURES REQUIREMENTS. EROSION BLANKETS MAY ALSO BE REQUIRED AT THE DISCRETION OF TOWN OFFICIALS OR PROJECT ENGINEER. WHEN STABILIZED BLANKET IS UTILIZED FOR CHANNEL STABILIZATION, PLACE ALL OF THE VOLUME OF SEED MIX PRIOR TO LAYING NET, OR AS RECOMMENDED BY THE MANUFACTURER.
- 13. TO PREVENT HEAVY CONSTRUCTION EQUIPMENT AND TRUCKS FROM TRACKING SOIL OFF-SITE, CONSTRUCT A PERVIOUS CRUSHED STONE PAD. LOCATE AND CONSTRUCT PADS AS DETAILED IN THESE PLANS.
- 14. CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED SOIL AREAS PERIODICALLY WITH WATER AS REQUIRED. CONTRACTOR TO SUPPLY ALL EQUIPMENT AND WATER.
- 15. CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION INSPECTIONS AS PER NYSDEC GP-0-15-002 AND TOWN OF OSSINING CODE.

MAINTENANCE OF TEMPORARY EROSION AND SEDIMENT CONTROL STRUCTURES: N.Y.S.D.E.C. GP-0-15-002 EXPOSURE RESTRICTIONS - STATES THAT ANY EXPOSED EARTHWORK SHALL BE STABILIZED IN ACCORDANCE WITH THE

GUIDELINES OF THIS PLAN.

- 1. TREES AND VEGETATION SHALL BE PROTECTED AT ALL TIMES AS SHOWN ON THE DETAIL DRAWING AND AS DIRECTED BY THE ENGINEER. 2. CARE SHOULD BE TAKEN SO AS NOT TO CHANNEL CONCENTRATED RUNOFF THROUGH THE AREAS OF CONSTRUCTION ACTIVITY ON THE SITE.
- 3. FILL AND SITE DISTURBANCES SHOULD NOT BE CREATED WHICH CAUSES WATER TO POND OFF SITE OR ON ADJACENT PROPERTIES. 4. RUNOFF FROM LAND DISTURBANCES SHALL NOT BE DISCHARGED OR HAVE THE POTENTIAL TO DISCHARGE OFF SITE WITHOUT FIRST BEING INTERCEPTED BY A CONTROL STRUCTURE, SUCH AS A SEDIMENT TRAP OR SILT FENCE. SEDIMENT SHALL BE REMOVED BEFORE EXCEEDING 50% OF
- THE RETENTION STRUCTURE'S CAPACITY. 5. FOR FINISHED GRADING, ADEQUATE GRADE SHALL BE PROVIDED SO THAT WATER WILL NOT POND ON LAWNS FOR MORE THAN 24 HOURS AFTER
- RAINFALL, EXCEPT IN SWALE FLOW AREAS WHICH MAY DRAIN FOR AS LONG AS 48 HOURS AFTER RAINFALL 6. ALL SWALES AND OTHER AREAS OF CONCENTRATED FLOW SHALL BE PROPERLY STABILIZED WITH TEMPORARY CONTROL MEASURES TO PREVENT EROSION AND SEDIMENT TRAVEL. SURFACE FLOWS OVER CUT AND FILL AREAS SHALL BE STABILIZED AT ALL TIMES.
- 7. ALL SITES SHALL BE STABILIZED WITH EROSION CONTROL MATERIALS WITHIN 7 DAYS OF FINAL GRADING. 8. TEMPORARY SEDIMENT TRAPPING DEVICES SHALL BE REMOVED FROM THE SITE WITHIN 30 DAYS OF FINAL STABILIZATION.

Existing topsoil will be removed and stored in piles sufficiently as to avoid mixing with other excavation. Stockpiles shall be surrounded by erosion control as outlined on these plans. The furnishing of new topsoil shall be of a better or equal to the following criteria (SS713.01 NYSDOT):

- 1. The pH of the material shall be 5.5 to 7.6.
- 2. The organic content shall not be less than 2% or more than 70%.

| 3. | Gradation: | SIEVE SIZE | <u>% PASSING BY WGT.</u> |
|----|------------|--------------|--------------------------|
| | | 2 INCH | 100 |
| | | 1 INCH | 85 TO 100 |
| | | 1/4 INCH | 65 TO 100 |
| | | NO. 200 MESH | 20 TO 80 |

PERMANENT VEGETATIVE COVER:

1. Site preparation:

- 1.1. Install erosion control measures. Scarify compacted soil areas. 1.2.
- 1.3. Lime as required to ph 6.5.
- 1.4. Fertilize with 10-6-4 4 lbs/1,000 S.F.
- 1.5. Incorporate amendments into soil with disc harrow. 2. Seed mixtures for use on swales and cut and fill areas.

| MIXTURE | | LBS. |
|---------|---------------------|------|
| ALT. A | KENTUCKY BLUE GRASS | |
| | CREEPING RED FESCUE | |
| | RYE GRASS OR REDTOP | |
| | | |

SEEDING

ALT. B

Prepare seed bed by raking to remove stones, twigs, roots and other foreign material.

TALL FESCUE/SMOOTH BLOOMGRASS

Apply soil amendments and integrate into soil. 3.2.

REDTOP

- Apply seed uniformly by cyclone seeder culti-packer or hydro-seeder at rate indicated. Stabilize seeded areas in drainage swales.
- Irrigate to fully saturate soil layer, but not to dislodge planting soil.

CREEPING RED FESCUE

- Seed between April 1st and May 15th or August 15th and October 15th. Seeding may occur May 15th and August 15th if adequate irrigation is provided.
- TEMPORARY VEGETATIVE COVER:

SITE PREPARATION:

1. Install erosion control measures.

4. Lime as required to ph 6.5.

2. Scarify areas of compacted soil. 3. Fertilize with 10-10-10 at 400/acre.


SEED SPECIES: <u>MIXTURE</u> Rapidly germinating annual ryegrass (or approved equal) Perennial ryegrass

SEEDING:

Cereal oats

Same as permanent vegetative cover

CONSTRUCTION SEQUENCE:



SURVEYOR, THESE INCLUDE THE BUILDING, LIMITS OF DISTURBANCE, UTILITY LINES, AND STORMWATER PRACTICES. 2. PRIOR TO THE START OF THE PROJECT, AN ON-SITE PRE-CONSTRUCTION MEETING WILL BE HELD. THIS WILL BE ATTENDED BY THE PROJECT OWNER, THE OPERATOR RESPONSIBLE FOR COMPLYING WITH THE APPROVED CONSTRUCTION DRAWINGS INCLUDING THE EROSION AND SEDIMENT CONTROL (E&SC) PLAN AND DETAILS, THE DESIGN ENGINEER, THE ENGINEER RESPONSIBLE FOR E&SC MONITORING DURING CONSTRUCTION, TOWN REPRESENTATIVES FROM THE ENGINEERING DEPARTMENT AND CODE ENFORCEMENT.

3. A LICENSED SURVEYOR MUST DEFINE INFRASTRUCTURE LOCATIONS, LIMITS OF DISTURBANCE, STORMWATER MANAGEMENT PRACTICE LIMITS, AND GRADES IN THE FIELD PRIOR TO START OF ANY CONSTRUCTION. LIMITS OF DISTURBANCE SHALL BE MARKED WITH THE INSTALLATION OF CONSTRUCTION FENCE OR APPROVED EQUAL. THE EXTENTS OF THE STORMWATER MANAGEMENT SYSTEM SHALL BE CORDONED OFF TO MINIMIZE THE DISTURBANCE ON THIS AREA.

4. INSTALL ALL PERIMETER EROSION CONTROL MEASURES, CONSTRUCTION ENTRANCE AS SHOWN ON THE EROSION AND SEDIMENT CONTROL PLAN AND THE ASSOCIATED DETAILS. INSTALL SILT FENCING AT THE BOTTOM OF SLOPES. THE STANDARDS ESTABLISHED IN PART 1.B 1.B OF THE GP-015-002 INCLUDED IN APPENDIX B OF THIS SWPPP MUST BE ADHERED TO.

5. STRIP SITE, CLEAR VEGETATION, AND PLACE TOPSOIL IN STOCKPILE LOCATIONS SHOWN ON THE PLAN. 6. BEGIN ROUGH GRADING THE SITE. CONTRACTOR TO LIMIT EXPOSURE OF DENUDED SOILS BY PROVIDING TEMPORARY STABILIZATION

FOR WORK AREAS THAT WILL REMAIN UNDISTURBED FOR OVER SEVEN (7) DAYS. CHIPPED ROCK THAT IS NOT SUITABLE TO REMAIN ON SITE SHALL BE HAULED AWAY AND PROPERLY DISPOSED OF. AN AREA HAS BEEN PROVIDED FOR THE STOCKPILING OF REMOVED SOIL AND ROCK WHICH IS TO BE REMOVED FROM THE SITE.

7. ROUGH GRADE THE DRIVEWAY ALONG THE SOUTHERN PROPERTY LINE TO ALLOW FOR THE INSTALLATION OF THE NEW STABILIZED

8. INSTALL STABILIZED CONSTRUCTION ENTRANCE AT LOCATION SHOW ALONG THE SOUTHERN PROPERTY LINE. 9. ROUGH GRADE BUILDINGS, DRIVEWAYS, AND PARKING AREAS. DURING THE GRADING OF THE DRIVEWAYS, CONSTRUCT THE RETAINING WALL ALONG THE SOUTHERN AND EASTERN PROPERTY LINES. BEFORE THE REAR PARKING LOT CAN BE CONSTRUCTED,

10. BEGIN CONSTRUCTION OF THE MAIN BUILDING. CONSTRUCTION OF THE REAR ACCESSORY BUILDING MAY BEGIN ONCE ENOUGH OF THE DRIVEWAYS HAVE BEEN ROUGH GRADED THAT THE BUILDING AREA MAY BE ACCESSED 11. BEGIN THE EXCAVATION AND INSTALLATION OF THE STORMWATER MANAGEMENT SYSTEM. PROTECT TRENCHES AND OPEN

EXCAVATIONS FROM EROSION. ENTRY INTO THE SYSTEM SHALL BE BLOCKED OFF UNTIL SITE HAS REACHED FINAL STABILIZATION. ONCE SYSTEM HAS BEEN INSTALLED. BACKFILL. SEED WHERE NECESSARY. AND REINSTALL MEASURES TO CORDON OFF THE SYSTEM FROM DISTURBANCE.

12. ONCE THE BUILDING FOUNDATION HAS BEEN INSTALLED, BEGIN CONSTRUCTION OF THE RETAINING WALL ON THE NORTH SIDE OF

13. DURING SITE CONSTRUCTION MAINTAIN AND RE-ESTABLISH AS REQUIRED EROSION CONTROL AND STABILIZATION MEASURES AS

REQUIRED BY THE SITE PLAN AND DETAILS. 14. EXCAVATE TO THE SUB-GRADE LEVEL. SCARIFY THE EXISTING SOIL TO A DEPTH OF 12-INCHES BY ROTOTILLING OR OTHER MEANS

ACCEPTABLE TO THE ENGINEER. INSTALL ALL COURSES OF STONE AS PER THE SPECIFICATIONS GIVEN ON THE PLAN. 15. INSTALL BASE COURSE OF ITEM 4 IN ALL PAVEMENT AREAS. STABILIZE ALL OPEN AREAS WITH SEED AND MULCH. 16. CONSTRUCT REMAINDER OF BUILDING, DRIVEWAY AND PARKING AREAS. FIRST INSTALL CURBS, ASPHALT BINDER, AND CONCRETE

SIDEWALK. ONCE BINDER COURSE IS INSTALLED, DRAINAGE OUTLET MAY BE UNBLOCKED. 17. BACKFILL CURBS, GRADE, PLACE FINAL SOIL TOPPING AND PUT IN PLACE PERMANENT VEGETATIVE COVER OVER ALL DISTURBED AREAS, LANDSCAPE BEDS, SLOPES, ETC.

18. ONCE SITE STABILIZATION HAS TAKEN PLACE (AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 80% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS), REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROLS, UNPLUG THE DRAINAGE SYSTEM TO ALLOW RUNOFF TO ENTER THE STORMWATER MANAGEMENT SYSTEM.

WINTER STABILIZATION NOTES:

IF CONSTRUCTION ACTIVITIES ARE EXPECTED TO EXTEND INTO OR OCCUR DURING THE WINTER SEASON THE CONTRACTOR SHALL ANTICIPATE PROPER STABILIZATION AND SEQUENCING. CONSTRUCTION SHALL BE SEQUENCED SUCH THAT WHEREVER POSSIBLE AREAS OF DISTURBANCE THAT CAN BE COMPLETED AND PERMANENTLY STABILIZED SHALL BE DONE BY APPLYING AND ESTABLISHING PERMANENT VEGETATIVE COVER BEFORE THE FIRST FROST. AREAS SUBJECT TO TEMPORARY DISTURBANCE THAT WILL NOT BE WORKED FOR AN EXTENDED PERIOD OF TIME SHALL BE TREATED WITH TEMPORARY SEED, MULCH, AND/OR EROSION BLANKETS.

OWNER / OPERATOR CERTIFICATION

INSTALL THE RETAINING WALL AT THE REAR OF THE SITE.

"I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. FURTHER, I HEREBY CERTIFY THAT THE SWPPP MEETS ALL FEDERAL, STATE, AND LOCAL EROSION AND SEDIMENT CONTROL REQUIREMENTS. I AM AWARE THAT FALSE STATEMENTS MADE HEREIN ARE PUNISHABLE AS A CLASS A MISDEMEANOR PURSUANT TO SECTION 210.45 OF THE PENAL LAW."

| NAME (PLEASE PRINT): | |
|----------------------|--|
| TITLE: | |
| DATE: | |
| ADDRESS: | |
| PHONE: | |
| E-MAIL: | |
| SIGNATURE: | |


CONTRACTOR CERTIFICATION STATEMENT

CERTIFICATION STATEMENT - ALL CONTRACTORS AND SUBCONTRACTORS AS IDENTIFIED IN A SWPPP, BY THE OWNER OR OPERATOR, IN ACCORDANCE WITH PART III.A.5 OF THE SPDES GENERAL PERMIT FOR STORMWATER RUNOFF FROM CONSTRUCTION ACTIVITY, GP-0-15-002. DATED JANUARY 12, 2015, PAGE 10 OF 40, SHALL SIGN A COPY OF THE FOLLOWING CERTIFICATION STATEMENT BEFORE UNDERTAKING ANY CONSTRUCTION ACTIVITY AT THE SITE IDENTIFIED IN THE SWPPP:

"I HEREBY CERTIFY THAT I UNDERSTAND AND AGREE TO COMPLY WITH THE TERMS AND CONDITIONS OF THE SWPPP AND AGREE TO IMPLEMENT ANY CORRECTIVE ACTIONS IDENTIFIED BY THE QUALIFIED INSPECTOR DURING A SITE INSPECTION. I ALSO UNDERSTAND THAT THE OWNER OR OPERATOR MUST COMPLY WITH THE TERMS AND CONDITIONS OF THE NEW YORK STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM ("SPDES") GENERAL PERMIT FOR STORMWATER DISCHARGE FROM CONSTRUCTION ACTIVITIES AND THAT IT IS UNLAWFUL FOR ANY PERSON TO CAUSE OR CONTRIBUTE TO A VIOLATION OF WATER QUALITY STANDARDS. FURTHERMORE, I UNDERSTAND THAT CERTIFYING FALSE, INCORRECT OR INACCURATE INFORMATION IS A VIOLATION OF THE REFERENCED PERMIT AND THE LAWS OF THE STATE OF NEW YORK AND COULD SUBJECT ME TO CRIMINAL, CIVIL AND/OR ADMINISTRATIVE PROCEEDINGS."


| INDIVIDUAL CONTRACTOR: |
|---------------------------------|
| NAME AND TITLE (PLEASE PRINT): |
| SIGNATURE OF CONTRACTOR: |
| COMPANY / CONTRACTING FIRM: |
| NAME OF COMPANY: |
| ADDRESS OF COMPANY: |
| TELEPHONE NUMBER / CELL NUMBER: |
| SITE INFORMATION: |
| ADDRESS OF SITE: |
| |
| TODAY'S DATE: |







9


TE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAV










NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW



NOT TO SCALE









DET

C-503





STORMTECH ENDCAP DETAIL

CONCRETE COLLAR

CONCRETE SLAB

" (150 mm) MIN THICKNESS


STORMTECH CHAMBER -


CORRUGATION VALLEY


UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION L

PROVIDED BY ADS)

PAVEMENT







П